

Name of Work : THE SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF EQUIPMENT FOR KITCHEN AND DINING FACILITIES OF HOSTEL NO. 19 AT IIT BOMBAY

PART D-2 : ABSTRACT OF PRICE

SR. NO.	ITEM DESCRIPTION	AMOUNT	REMARKS
PART I	SERVICE AREA	32,94,833.00	
PART II	HOT KITCHEN	64,80,866.00	
PART III	EXHAUST HOOD	25,30,699.00	
PART IV	GRATING	18,63,147.00	
PART V	BUTCHERY	1,52,256.00	
PART VI	VEG PREPARATION	11,10,968.00	
PART VII	COLD ROOM	12,00,125.00	
PART VIII	FREEZER ROOM	10,56,780.00	
PART IX	MASALA SECTION	7,06,236.00	
PART X	DISH WASH AREA	55,44,591.00	
PART XI	POT WASH	48,06,075.00	
PART XII	RECEIVING AREA	8,42,353.00	
PART XIII	OIL STORAGE	98,090.00	
PART XIV	GRAIN STORAGE	78,528.00	
PART XV	DRY STORAGE	7,43,791.00	
PART XVI	WASTE BIN	2,44,782.00	
PART XVII	WATER COOLER SECTION	53,898.00	
PART XVIII	FIRST FLOOR DRY STORAGE	3,34,189.00	
PART XIX	FIRE SUPPRESSION SYSTEM	25,45,332.00	
PART XX	MISCELLEANOUS	43,97,155.00	
	TOTAL AMOUNT (WITHOUT GST) -	3,80,84,694	A
	ADD GST @ 18% -	68,55,245	B
	TOTAL AMOUNT INCLUDING GST	4,49,39,939	C=(A+B)

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY, POWAI, MUMBAI- 400076

**THE SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF EQUIPMENT FOR KITCHEN AND DINING FACILITIES OF
HOSTEL NO. 19 AT IIT BOMBAY**

PART D-2 : BILL OF QUANTITIES

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
PART I						
SERVICE AREA						
1	S1	Supply , Installation, Testing & Commissioning of custom fabricated stainless steel HOT BAIN MARIE COUNTER WITH HOT CASE BELOW of Size 1850 mm X (700+325) mm X (850+ 550) mm with GN pans & Lids, Sneeze guard, water chambers, perforated bottom selves, immersion heaters, tray rails, legs and framework i/c connections etc complete as per the specifications mentioned in the corresponding drawing	SET	3	1,44,524.00	4,33,572.00
2	S1A	Supply , Installation, Testing & Commissioning of custom fabricated stainless steel HOT BAIN MARIE COUNTER of Size 1850 mm X (700+325) mm X (850+ 550) mm with GN pans & Lids, Sneeze guard, water chambers, perforated bottom selves, tray rails, legs and framework i/c connections etc complete as per the specifications mentioned in the corresponding drawing	SET	2	1,16,326.00	2,32,652.00
3	S1B	Supply , Installation, Testing & Commissioning of custom fabricated stainless steel HOT BAIN MARIE COUNTER FOR JAIN- of Size 2050 mm X (700+325) mm X (850+ 550) mm with GN pans & Lids, Sneeze guard, water chambers, perforated bottom selves, tray rails, legs and framework i/c connections etc complete as per the specifications mentioned in the corresponding drawing	SET	1	1,24,891.00	1,24,891.00
4	S2	Supplying and placing of custom fabricated Stainless steel SALAD COUNTER of size 800 mm X (700+325) mm X (850+ 550)mm with 2 no Under shelves, sneeze guard, tray rails, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	73,486.00	2,93,944.00
5	S3	Supplying and placing of custom fabricated stainless steel PLATE DISPENSING TABLE WITH 2 U/S of size 750 mm X (700+325) mm X (850+ 550) mm with 2 no Under shelves, Sneeze guard ,tray rails, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	46,581.00	1,39,743.00
6	S4	Supplying and placing of custom fabricated stainless steel PLATE DISPENSING TABLE WITH 2 U/S of size 1050 mm X (700+325) mm X (850+ 550) mm with 2 no Under shelves, Sneeze guard ,tray rails, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	58,824.00	58,824.00
7	S5	Supplying and placing of the CUTLERY BOX of minimum size 17" X 10½" X 3¾" made of ABS plastic having four compartments on existing Plate Dispensing Table as per the specifications mentioned in the corresponding drawing.	SET	4	2,845.00	11,380.00
8	S6	Supplying and placing of custom fabricated Stainless steel WORK COUNTER WITH 2 U/S of size 1500 mm X (700+325) mm X (850+ 550)mm with 2 no Under shelves, sneeze guard, tray rails, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	71,870.00	71,870.00
9	S7	Supply, Installation, Testing & Commissioning of CONVEYOR TOASTER of minimum capacity 1000 slices/hr suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	3,34,119.00	13,36,476.00
10	S8	Supplying and placing of custom fabricated stainless steel TEA COFFEE STATION WITH 2 U/S of size 1250 mm X (700+325) mm X (850+ 550) mm with 2 no Under shelves ,sunk in top, sneeze guard, trail rails, legs and framework etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	61,214.00	61,214.00
11	S9	Supplying and placing of custom fabricated Stainless steel WORK COUNTER WITH 2 U/S of size 1350 mm X (700+325) mm X (850+ 550)mm with 2 no Under shelves, sneeze guard, tray rails, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	68,604.00	68,604.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
12	S10	Supply, Installation, Testing & Commissioning of convection type MICROWAVE of minimum 30 litres capacity with stainless steel body suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	26,493.00	1,05,972.00
13	S11	Supplying and placing of custom fabricated Stainless steel WORK COUNTER WITH 2 U/S of size 1000 mm X 700 mm X 850mm with 2 no Under shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	42,869.00	42,869.00
14	S12	Supplying and placing custom fabricated Stainless Steel TRAY RACK FIVE SHELVES of size 900 mm X 700 mm X 1800 mm made of 16 SWG sheet with 5 no Shelves etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	45,938.00	1,37,814.00
15	S13	Supplying and placing of custom fabricated Stainless steel WORK COUNTER FOR TOASTER of size 1200 mm X 700 mm X 850mm with 2 no Under shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding	SET	1	46,581.00	46,581.00
16	S14	Supplying and placing of custom fabricated Stainless steel WORK COUNTER FOR TOASTER of size 1800 mm X 700 mm X 850mm with 2 no Under shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding	SET	1	56,361.00	56,361.00
17	S15	Supplying and placing of custom fabricated Stainless steel WORK COUNTER FOR MICROWAVE of size 730 mm X 600 mm X 850mm with 2 no Under shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding	SET	2	36,033.00	72,066.00
TOTAL OF SERVICE AREA						32,94,833.00
PART II		HOT KITCHEN				
1	HK1	Supply, Installation, Testing & Commissioning of custom fabricated double door stainless steel Vertical Freezer of 500 Ltrs. Capacity suitable for operation on 230 volts/50 Hz single phase A.C. supply and having GN pans on angles, 8 no wire shelves ,insulation, hermetically sealed compressor, legs and drain plate i/c connections etc complete as per the specifications mentioned in the corresponding drawing. .The internal temperature shall be maintained in the range of -18° C to -22° C	SET	2	1,03,657.00	2,07,314.00
2	HK2	Supply, Installation, Testing & Commissioning of custom fabricated double door stainless steel Vertical Refrigerator of 500 Ltrs. Capacity suitable for operation on 230 volts/50 Hz single phase A.C. supply and having GN pans on angles, 8 no wire selves, insulation, hermetically sealed compressor ,legs and drain plate i/c connections etc complete as per the specifications mentioned in the corresponding drawing. The internal temperature shall be maintained in the range of +4° C to +8° C	SET	2	93,899.00	1,87,798.00
3	HK3	Supplying and placing of custom fabricated Stainless Steel WORK TABLE WITH CROSS BRACING of size 1800 mm X 700 mm X (850+ 150) mm made up of 14 SWG sheet with splash back and having Cross Bracing ,legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	30,056.00	30,056.00
4	HK4	Supplying and placing of custom fabricated Stainless Steel Flour Bin on dolly of size 500 mm X 600 mm X 700 mm having SS rod collapsable handle, castors with brakes and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	29,412.00	88,236.00
5	HK5	Supplying and placing of custom fabricated Stainless Steel Masala Trolley of size 500 mm X 800 mm X 850 mm with 9 nos. GN pans, 1 no undershelf, castors with brakes - rubber bumpers and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	2	29,205.00	58,410.00
6	HK6	Supply, Installation, Testing & Commissioning of COMBI OVEN 20 TRAY 1/1 GAS SIZE: 879X931X1807MM - Capacity 20 x 1/1 GN,Number of meals per day 150–300, Lengthwise loading 1/1, 1/2, 2/3, 1/3, 2/8 GN Width 877 mm, Depth 913 mm, Height 1807 mm Water inlet, R 3/4", Water outlet DN 50 Water pressure 1,0 - 6,0 bar as per the specifications mentioned in the corresponding drawing..	SET	1	21,81,906.00	21,81,906.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
7	HK6A	Supply, Installation, Testing & Commissioning of COMBI OVEN TROLLEY 201 SIZE: 561x824x1743MM o• Compatible with 201 combi ovens.• Made from high grade stainless steel. • The low rack height of no more than 1.60m allows the unit to be loaded & unloaded quickly. Oversized, quiet & hygienic tandem castors for easy movement. • Standard 20 racks, 15 racks (84mm), 16 racks (80mm), 17 racks (74mm) or bakery standard options available as per the specifications mentioned in the corresponding drawing..	SET	2	2,73,166.00	5,46,332.00
8	HK7	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel Tilting Bracing Pan of 150 liters capacity having tilting bracing pan ,control panel , 2 Nos. V-900 burner compatible with PNG gas, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	2,60,199.00	5,20,398.00
9	HK7A	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel Tilting Bracing Pan of 80 liters capacity having tilting bracing pan ,control panel , 2 Nos. V-900 burner compatible with PNG gas, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	2,15,989.00	2,15,989.00
10	HK8	Supplying and placing of custom fabricated stainless steel MOBILE TABLE of size 800 mm X 750 mm X 850 mm with 2 no Undershelves ,legs with castors with brakes and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	3	26,949.00	80,847.00
11	HK9	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 800 mm X 800 mm X (850+150) mm with splash back having sink of size 450 mm X 450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	34,338.00	34,338.00
12	HK10	Supply , Installation, Testing & Commissioning of Stainless Steel gas operated IDLI PLANT WITH STAND for steaming minimum 300 Idli/ batch with gas pressure regulator, control panel, suitable burner compatible with PNG gas, exhaust for excessive heat and steam drain, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	97,943.00	1,95,886.00
13	HK11	Supplying and placing of custom fabricated stainless steel KITCHEN UTILITY TROLLEY of size 700 mm X 1050 mm X 1000 mm having 16 SWG SS tray type shelves, castors with brakes-bumpers etc complete as per the specifications mentioned in the corresponding drawing	SET	3	33,695.00	1,01,085.00
14	HK12	Supply, Installation, Testing & Commissioning of dual speed DOUGH KNEADER CAP-40 KG (flour) capacity having stainless steel heavy duty detachable and rotating drum along with M.S angle frame work, control panel, motor and starter suitable for operation on 415 volts/50 Hz 3- phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	86,779.00	1,73,558.00
15	HK13	Supply , Installation, Testing & Commissioning of custom fabricated stainless steel DOSA PLATE WITH 1 U/S of size 1200 mm X 800 mm X (850+150) mm having 1 no Undershelf with 4 nos V-600 burners , pilots and gas inlet at rear grease collecting drawer, drip tray, griddle plate , grease trough, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	48,971.00	1,95,884.00
16	HK14	Supplying and placing of custom fabricated stainless steel WORK TABLE WIH 2 U/S of size 700 mm X 800 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	3	26,949.00	80,847.00
17	HK14A	Supplying and placing of custom fabricated stainless steel WORK TABLE WIH 2 U/S of size 1000 mm X 800 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	31,875.00	31,875.00
18	HK15	Supplying and placing of custom fabricated stainless steel WORK TABLE WIH 2 U/S of size 1350 mm X 700 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	36,728.00	36,728.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
19	HK16	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel 4 Burner gas Range of size 900 mm X 900 mm X (850+150) having splash on rear side, front control panel, drip tray, legs and frame work. It shall have 1 no. High pressure T-35 burner, 1 no. High pressure T-22 burner, and 2 no. low pressure burners compatible with PNG gas etc complete as per the specifications mentioned in the corresponding drawing. It shall be provided complete with gas connection and all accessories.	SET	1	48,971.00	48,971.00
20	HK17	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 900 mm X 700 mm X (850+150) mm with splash back having sink of size 450 mm X 450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	30,626.00	30,626.00
21	HK18	Supplying and placing of custom fabricated stainless steel GN PAN TROLLEY of size 600 mm X 675 mm X 1800 mm with 20 pair of angles which are at 75 mm clear distance from each other to hold 2 no. 1/1 gn pans, castors with brakes etc complete as per the specifications mentioned in the corresponding drawing	SET	1	29,412.00	29,412.00
22	HK19	Supply, Installation, Testing & Commissioning of custom fabricated Stainless Steel CHAPATTI PLATE PUFFER WITH 1 U/S of size 1300 mm X 750 mm X (850 +150) mm having 1 Under shelve , Mild steel chapati plate of size 900 mm x 700 mm x 25 mm and Cast iron puffer plate of size 300 mm X 700 mm 40 mm. It shall have 2 nos. V- burners (V-750 mm & V-600 mm long with pilot) compatible with PNG gas,, 1 no underself ,Legs and frame work etc complete as per the specifications mentioned in the corresponding drawing. It shall be provided complete with gas connection and all accessories.	SET	3	56,361.00	1,69,083.00
23	HK20	Supplying and placing of custom fabricated stainless steel WORK TABLE WIH 2 U/S of size 750 mm X 750 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	4	26,949.00	1,07,796.00
24	HK21	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel SINGLE BURNER GAS RANGE of size 900 mm X 900 mm X 550 mm with High pressure multi ring burner compatible with PNG gas, gas inlet on both rear sides, drip tray, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing. It shall be provided complete with gas connection and all accessories.	SET	8	37,978.00	3,03,824.00
25	HK21A	Supply , Installation, Testing & Commissioning of WALL MOUNTED POT FILLER having chrome plated brass body, 24" double joint swing nozzle, on-off volume control outlet with insulated grip, 1/2" NPT female inlet etc complete as per the specifications mentioned in the corresponding drawing.	SET	8	31,460.00	2,51,680.00
26	HK22	Supply , Installation, Testing & Commissioning of custom fabricated Stainless Steel BULK KADAI UNIT of size 900 mm X 900 mm X 550 mm having heavy duty MS frying Kadai, High pressure multi ring burner compatible with PNG gas, gas inlet on both rear sides, drip tray, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing. It shall be provided complete with gas connection and all accessories.	SET	1	48,401.00	48,401.00
27	HK23	Supplying and placing of custom fabricated stainless steel UTENSIL TROLLEY of size 900 mm X 900 mm X 500 mm having removable tray, castors with breaks etc complete as per the specifications mentioned in the corresponding drawing	SET	4	22,096.00	88,384.00
28	HK24	Supplying and Placing of custom fabricated stainless steel MARBLE TOP CHAPATTI ROLLING TABLE ON WHEEL of size 1500 mm X 900 mm X 850 mm having marble top, crossing bracing, legs ,castors with brakes etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	34,338.00	1,03,014.00
29	HK25	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 1500 mm X 700 mm X (850+150) mm with splash back having sink of size 450 mm X 450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	39,192.00	39,192.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
30	HK26	Supplying and placing of custom fabricated stainless steel WORK TABLE WITH 2 U/S of size 1800 mm X 800 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	53,898.00	53,898.00
31	HK27	Supply , Installation, Testing & Commissioning of custom fabricated stainless steel Tilting Rice Boiler of 160 Liters capacity having tilting boiling pan with spring loaded and insulated lid ,single swivel faucet, tilting mechanism with worm gear, ignition aperture and 3 nos T-35 burners compatible with PNG gas etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	2,39,098.00	2,39,098.00
TOTAL OF HOT KITCHEN						64,80,866.00
PART III		EXHAUST HOOD				
1	EX1	Supply, Installation, Testing & Commissioning of custom fabricated EXHAUST HOOD WITH FRESH AIR FOR TILTING PAN of size 10400 mm X 1400 mm X 600 mm made up of SS 304 body and having frame work, grease filter, bulk head lights with fire proof wiring complete with all accessories for fixing the hood from ceiling etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	6,04,825.00	6,04,825.00
2	EX2	Supply, Installation, Testing & Commissioning of custom fabricated EXHAUST HOOD WITH FRESH AIR FOR BOILING PAN of size 4800 mm X 1600 mm X 600 mm made up of SS 304 body and having frame work, grease filter, bulk head lights with fire proof wiring complete with all accessories for fixing the hood from ceiling etc complete as per the specifications mentioned in the corresponding drawing	SET	1	3,18,313.00	3,18,313.00
3	EX3	Supply, Installation, Testing & Commissioning of custom fabricated EXHAUST HOOD WITH FRESH AIR FOR IDLI & BURNER of size 3500 mm X 1600 mm X 600 mm made up of SS 304 body and having frame work, grease filter, bulk head lights with fire proof wiring complete with all accessories for fixing the hood from ceiling etc complete as per the specifications mentioned in the corresponding drawing	SET	1	2,42,467.00	2,42,467.00
4	EX4	Supply, Installation, Testing & Commissioning of custom fabricated EXHAUST HOOD WITH FRESH AIR FOR SINGLE BURNERS of size 10400 mm X 1500 mm X 600 mm made up of SS 304 body and having frame work, grease filter, bulk head lights with fire proof wiring complete with all accessories for fixing the hood from ceiling etc complete as per the specifications mentioned in the corresponding drawing	SET	1	6,61,113.00	6,61,113.00
5	EX5	Supply, Installation, Testing & Commissioning of custom fabricated EXHAUST HOOD WITH FRESH AIR FOR CHAPATI PLATE of size 10400 mm X 1300 mm X 600 mm made up of SS 304 body and having frame work, grease filter, bulk head lights with fire proof wiring complete with all accessories for fixing the hood from ceiling etc complete as per the specifications mentioned in the corresponding drawing	SET	1	5,75,413.00	5,75,413.00
6	EX6	Supply, Installation, Testing & Commissioning of custom fabricated VAPOUR HOOD FOR DISH WASHER of size 3150 mm X 1000 mm X 600 mm made up of SS 304 body and having frame work, grease filter, bulk head lights with fire proof wiring complete with all accessories for fixing the hood from ceiling etc complete as per the specifications mentioned in the corresponding drawing	SET	1	1,28,568.00	1,28,568.00
TOTAL OF EXHAUST HOOD						25,30,699.00
PART IV		GRATING				
1	G1	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 600 mm X 600 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	17,169.00	68,676.00
2	G2	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 10800 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	1,54,304.00	4,62,912.00
3	G3	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 6100 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	89,413.00	89,413.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
4	G4	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 11375 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	1,64,083.00	1,64,083.00
5	G5	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 13800 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	1,98,348.00	1,98,348.00
6	G6	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 3060 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	44,118.00	44,118.00
7	G7	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 3700 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	53,898.00	1,07,796.00
8	G8	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 7650 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	1,12,649.00	1,12,649.00
9	G9	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 5400 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	77,170.00	77,170.00
10	G10	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 1600 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	22,666.00	45,332.00
11	G11	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 1200 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	6	17,169.00	1,03,014.00
12	G12	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 2400 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	34,338.00	1,03,014.00
13	G13	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 8000 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	1,16,326.00	1,16,326.00
14	G14	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 3000 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	42,869.00	42,869.00
15	G15	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 1750 mm X 300 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	25,735.00	25,735.00
16	G16	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 2340 mm X 200 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	34,338.00	34,338.00
17	G17	Supply, Installation, Testing & Commissioning of custom fabricated GRATING WITH PERFORATED BASKET of size 4700 mm X 200 mm made up of SS 304 material etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	67,354.00	67,354.00
TOTAL OF GRATING						18,63,147.00
PART V		BUTCHERY				
1	B1	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 1100 mm X 600 mm X (850+150) mm with splash back having sink of size 450 mm X 450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	36,728.00	36,728.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
2	B2	Supplying and placing of the GARBAGE BIN of 80 liters capacity with diameter 440 mm (Top) and minimum height 700 mm as per the specifications mentioned in the corresponding drawing.	SET	1	7,996.00	7,996.00
3	B3	Supplying and placing of custom fabricated CHOPPING BOARD STERLIZER of size 450 mm X 600 mm X 700 mm made up of SS 304 material having chopping board stackers, base frame, sink, cross bracing, legs castors with brakes and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	26,949.00	26,949.00
4	B4	Supplying and placing of custom fabricated stainless steel CHOPPING BLOCK of size 600 mm X 600 mm X 850 mm with 75 mm chopping block thickness made up of Ferro nylon material and having channel, cross bracing, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	29,412.00	29,412.00
5	B5	Supplying and placing of WEIGHING SCALE TABLE TOP having load capacity 30 Kg with accuracy of 1 gm and stainless steel platform with minimum size of 215 mm X 265 mm suitable for operation on 230 volts/50 Hz single phase A.C. supply having multifunction keyboard and other features etc complete as per the specifications mentioned in the corresponding drawing	SET	1	8,302.00	8,302.00
6	B6	Supplying and placing of custom fabricated stainless steel WORK TABLE WITH 2 U/S of size 1750 mm X 600 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	42,869.00	42,869.00
TOTAL OF BUTCHERY						1,52,256.00
PART VI		VEG PREPARATION				
1	VP1	Supplying and placing of custom fabricated stainless steel MOBILE TABLE WITH 2 U/S of size 1500 mm X 800 mm X 850 mm with 2 no Undershelves ,legs with castors with brakes and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	2	41,655.00	83,310.00
2	VP2	Supplying and placing of custom fabricated stainless steel WORK TABLE WITH 2 U/S of size 1800 mm X 700 mm X (850+150) mm with splash back ,having 2 no under-Shelves, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	3	45,332.00	1,35,996.00
3	VP3	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 1650 mm X 700 mm X (850+150) mm with splash back having sink of size 450 mm X 450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	41,655.00	41,655.00
4	VP4	Supply, Installation, Testing & Commissioning of VEG. PROCESSOR - ROBOT COUPE capable of continuous feed slicing, dicing, shredding, grating, French fry and Julienne supplied with hopper and standard set of discs for different application, processing speed up to 550 Kg/hr, single speed, 340 ~ 375 RPM motor with power of 550 W suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	2,65,361.00	5,30,722.00
5	VP5	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 1800 mm X 700 mm X (850+150) mm with splash back having sink of size 700 mm X 500 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	44,118.00	44,118.00
6	VP6	Supplying and placing of custom fabricated CHOPPING BOARD STERLIZER of size 600 mm X 600 mm X 700 mm made up of SS 304 material having chopping board stackers, base frame, sink, cross bracing, legs castors with brakes and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	26,949.00	26,949.00
7	VP7	Supplying and placing of the GARBAGE BIN of 80 liters capacity with diameter 440 mm (Top) and minimum height 700 mm as per the specifications mentioned in the corresponding drawing.	SET	1	7,996.00	7,996.00
8	VP8	Supplying and placing of custom fabricated STORAGE RACK FIVE SHELVES of size 1000 mm X 600 mm X 1800 mm having Five Shelves made up of 18 SWG SS 304 sheet equidistant from each other, uprights with S.S. square pipes etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	31,875.00	63,750.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
9	VP9	Supplying and placing of custom fabricated ONION,COCONUT,POTATO BIN of size 750 mm X 700 mm X 1000 mm with 14 SWG SS top, 25 mm X 25 mm -14 SWG wire mesh on all sides, cross bracings, Tray, castors with brakes - bumpers and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	44,118.00	1,76,472.00
TOTAL OF VEG PREPARATION						11,10,968.00
PART VII		COLD ROOM				
1	CR1	Supply, Installation, Testing & Commissioning of custom fabricated COLD ROOM of size 4850 mm X 3350 mm X 2700 mm with internal desired temperature of +2°C to +8°C and minimum refrigeration capacity 3 KW, Panel insulation i/c connections etc complete as per the specifications mentioned in the corresponding drawing	SET	1	8,52,145.00	8,52,145.00
2	CR2	Supplying and placing of custom fabricated Stainless steel COLD ROOM RACK FIVE SHELVES of size 1500mm X 650 mm X 1800 mm having Five Shelves made up of 18 SWG perforated sheet equidistant from each other, uprights and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	48,401.00	1,93,604.00
3	CR3	Supplying and placing of custom fabricated Stainless steel COLD ROOM RACK THREE SHELVES of size 1500mm X 650 mm X 1800 mm having Five Shelves made up of 18 SWG perforated sheet equidistant from each other, uprights and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	36,728.00	36,728.00
4	CR5	Supplying and placing of custom fabricated Stainless steel VEG RACK TROLLEY of size 500mm X 650 mm X 1850 mm with 9 pairs of 35 mm X 35 mm X 14 SWG SS angles for stacking of baskets, uprights, castors with brakes-bumpers and along with 9 no crates etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	31,875.00	63,750.00
5	CR6	Supplying and placing of custom fabricated stainless steel GN PAN TROLLEY of size 600 mm X 675 mm X 1800 mm with 20 pair of angles which are at 75 mm clear distance from each other to hold 2 no. 1/1 gn pans, castors with brakes etc complete as per the specifications mentioned in the corresponding drawing	SET	2	26,949.00	53,898.00
TOTAL OF COLD ROOM						12,00,125.00
PART VIII		FREEZER ROOM				
1	FR1	Supply, Installation, Testing & Commissioning of FREEZER ROOM of size 2800 mm X 3350 mm X 2700 mm with internal desired temperature of -24°C to - 20°C and minimum refrigeration capacity 4.5 KW. Panel insulation and other features shall be as per the specifications mentioned in the corresponding drawing. The freezer room shall be complete with drainage, electrical system and other required accessories.	SET	1	8,79,020.00	8,79,020.00
2	FR2	Supplying and placing of custom fabricated Stainless steel COLD ROOM RACK FIVE SHELVES of size 1200mm X 650 mm X 1800 mm having Five Shelves made up of 18 SWG perforated sheet equidistant from each other, uprights and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	5	35,552.00	1,77,760.00
TOTAL OF FREEZER ROOM						10,56,780.00
PART IX		MASALA SECTION				
1	MS1	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 1500 mm X 700 mm X (850+150) mm with splash back having sink of size 450 mm X 450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc complete as per the specifications mentioned in the corresponding	SET	1	36,728.00	36,728.00
2	MS2	Supplying and placing of the GARBAGE BIN of 80 liters capacity with diameter 440 mm (Top) and minimum height 700 mm as per the specifications mentioned in the corresponding drawing.	SET	1	7,996.00	7,996.00
3	MS4	Supply, Installation, Testing & Commissioning of Tilttable WET MASALA GRINDER of capacity 25 Kg made up of SS 304 grade material with 3. KW electric motor and starter suitable for operation on 3-phase,415 volts,50 Hz A.C. supply, cross bracing and frame work i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	1,59,739.00	3,19,478.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
4	MS5	Supply, Installation, Testing & Commissioning of PULVERISER (7.5 HP) made up of SS 304 grade material with directly coupled 3 phase electric motor and starter suitable for operation on 3-phase,415 volts,50 Hz A.C. supply, powerful crusher with doors, container, control panel,1 no GN container, cross bracing and frame work i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	61,214.00	1,22,428.00
5	MS6	Supply, Installation, Testing & Commissioning of POTATO PEELER of 20 Kg capacity made up of SS304 grade material having SS drum, sproutlid, lockable lid, sunk on top , legs, frame work, control panel and motor with starter suitable for operation on 3-phase,415 volts,50 Hz A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	53,898.00	1,07,796.00
6	MS7	Supply, Installation, Testing & Commissioning of custom fabricated Stainless steel POTATO PEELING SINK of size 600 mm X 600 mm X 600 mm with Sink of size 500 mm X 500 mm X 400 mm deep, strainer basket, legs, cross bracing, frame work, castors with brakes & bumpers i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	24,486.00	48,972.00
7	MS8	Supply , Installation, Testing & Commissioning of WALL MOUNTED POT FILLER having chrome plated brass body, 18" double joint swing nozzle, on-off volume control outlet with insulated grip, 1/2" NPT female inlet etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	31,419.00	62,838.00
TOTAL OF MASALA SECTION						7,06,236.00
PART X		DISH WASH AREA				
1	DW1	Supply, Installation, Testing & Commissioning of custom fabricated SOILED DISH RECEIVER WITH OHS of size 2000 mm X 800 mm X (850+500) mm made of SS 304 grade material with sunk in top, cross bracing, legs and frame work etc complete including connections as per the specifications mentioned in the corresponding drawing.	SET	1	42,869.00	42,869.00
2	DW2	Supplying and placing of the GARBAGE BIN of 80 liters capacity with diameter 440 mm (Top) and minimum height 700 mm as per the specifications mentioned in the corresponding drawing.	SET	2	7,996.00	15,992.00
3	DW3	Supply, Installation, Testing & Commissioning of custom fabricated SS 304 ENTRY TABLE THREE SINK of size 1800 mm X 700 mm X (850+250) mm with splash back, 16 SWG 3 no Sinks in top of size 450 mm X 450 mm X300 mm deep, strainer basket, cross bracing ,legs and frame work i/c connections etc complete as per the specifications mentioned in the corresponding drawing	SET	1	51,435.00	51,435.00
4	DW4	Supply, Installation, Testing & Commissioning of HAND SPRAY T&S 6" to 8" deck mount mixing faucet with polished chrome plated brass body, 21" to 24" riser, minimum 36" flexible stainless steel hose, heat resistant handle, 1.15 GPM spray valve, compression cartridges with spring checks, lever handles, 1/2" NPT female inlets, 6" adjustable wall bracket including connections as per the specifications mentioned in the corresponding drawing.	SET	1	33,089.00	33,089.00
5	DW6	Supply, Installation, Testing & Commissioning of DISH WASHER WITH DRYER TR600 WORKING DIRECTION RIGHT TO LEFT having theoretical Rack capacity / hr of 125/190/250 with 3 transport speeds for racks of dimension 500 mm X 500 mm suitable for operation on 440 volts 3-phase A.C. supply. It shall be complete with plumbing, drainage, electrical system and other accessories i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	46,43,524.00	46,43,524.00
6	DW6A	Supply, Installation, Testing & Commissioning of Ion exchange resin type SOFTNER (CANATURE CS15H- 1035) compatible with dish washer machine suitable for 230 volts/50 Hz single phase A.C supply including connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	1,01,163.00	1,01,163.00
7	DW7	Supplying and placing of custom fabricated Stainless Steel EXIT TABLE WITH STACKER of size 1550 mm X 700 mm X 850+250 mm with 14 SWG sheet sunk in top with splash back, cross bracings, angles, legs and frame work etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	36,728.00	36,728.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
8	DW7A	Supplying and placing of custom fabricated Stainless Steel WORK TABLE WITH CROSS BRACING of size 600 mm X 700 mm X (1150+ 150) mm made up of 14 SWG sheet with splash back and having Cross Bracing ,legs and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	1	12,243.00	12,243.00
9	DW8	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size1200 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	35,552.00	1,42,208.00
10	DW8A	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size950 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	30,626.00	30,626.00
11	DW9	Supplying and placing of custom fabricated CHEMICAL CUPBOARD STORAGE FIVE SHELVES of size 1200 mm X 600 mm X 1800 mm having five shelves made up of 16 SWG SS sheet ,2 no doors, castors with brake & bumpers etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	79,597.00	79,597.00
12	DW10	Supplying and placing of custom fabricated THALI TROLLEY of size (1650+100) mm X 475 mm X 1450 mm with 16 SWG SS top and 50 nos. 6 mm SS solid holding rod at 32 mm distance between two rods to hold thali tray, S.S. round handle, S.S plates fixed to castors, castors with brakes and bumpers etc complete as per the specifications mentioned in the corresponding drawing.	SET	5	51,435.00	2,57,175.00
13	DW11	Supplying and placing of custom fabricated TIFFIN TROLLEY of size (1100+100) mm X 600 mm X 1250 mm made up of 34 nos. 6 mm SS solid holding rod at 32 mm distance between two rods to hold thali tray, S.S. round handle, S.S plates fixed to castors, castors with brakes and bumpers etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	48,971.00	97,942.00
TOTAL OF DISH WASH AREA						55,44,591.00
PART XI		POT WASH				
1	PW3	Supply, Installation, Testing & Commissioning of WALL MOUNTED MIXING FAUCET- 8" Wall Mount Mixing Faucet, Quarter-Turn Ceramic Cartridges, equip Lever Handles,12" equip Swing Nozzle & 1/2" NPT Female Inlets as per the specifications mentioned in the corresponding drawing.	SET	2	16,412.00	32,824.00
2	PW4	Supplying and placing of custom fabricated POT RACK FOUR SHELVES of size 1500 mm X 800 mm X 1650 mm having four shelves made up of SS 304 grade material with round pipes for intercross, supports and upright etc complete as per the specifications mentioned in the corresponding drawing.	SET	6	44,118.00	2,64,708.00
3	PW5	Supply, Installation, Testing & Commissioning of POT WASHER- compact edition /flow edition /free flow edition weight (filled/ empty) 666 kg/485 kg wash tank volume : 165 liters rinse water volume : 7 liters (eco programme) 14 liters (short /normal programme) granule volume : 16 liters max. / normal capacity per hour : 192/136 (compact) /192/144 (normal capacity incl. handling) (flow)/ 192/160 (free flow) capacity per programme : 8 gn 1/1 or up to 16 gn 1/2 or 4 gn 2/1 up to 200 mm depth or similar in other pots. as per the specifications mentioned in the corresponding drawing.	SET	1	40,40,133.00	40,40,133.00
4	PW6	Supply, Installation, Testing & Commissioning of POT WASHER TROLLEY - cassette size :- 640x700x1100mm trolley size :- 610x1141x1365mm cassette trolley. art no. 22845 for operation of multi-cassette. multi-cassette for granule maxi flow/ freeflow. art no. 14469 for 8 gn 1/1 containers or 4 gn 2/1 or equivalent in other washware. as per the specifications mentioned in the corresponding drawing.	SET	2	2,34,205.00	4,68,410.00
TOTAL OF POT WASH						48,06,075.00
PART XII		RECEIVING AREA				

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
1	R1	Supplying and placing of Heavy duty platform WEIGHING SCALE FLOOR MODEL upto150 Kg load capacity with accuracy of 10 gm and Stainless steel platform of minimum size 400 mm X 500 mm suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	15,654.00	15,654.00
2	R2	Supplying and placing of custom fabricated Stainless steel KITCHEN UTILITY TROLLEY of size 900 mm X 750 mm X 1000 mm with 16 SWG SS tray type shelves, castors with brakes-bumpers etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	28,198.00	56,396.00
3	R3	Supplying and placing o f custom fabricated Stainless steel PLATFORM TROLLEY of size 1200 mm X 750 mm X 900 mm with 16 SWG SS base and 1½" diameter SS pipe handle ,frame work, castors with brakes-bumpers etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	19,632.00	39,264.00
4	R4	Supply, Installation, Testing & Commissioning of VEGETABLE WASHER TILTING :- total watts: 1.6kw usable well capacity:500liters load per cycle –leafy vegetables:14kg load per cycle –heavy vegetables:70kg external dimensions: length:1500 external dimensions: width:877 external dimensions: height:845 shipping weight : 250 kg as per the specifications mentioned in the corresponding drawing.	SET	1	6,88,705.00	6,88,705.00
5	R5	Supplying and placing of the GARBAGE BIN of 80 liters capacity with diameter 440 mm (Top) and minimum height 700 mm as per the specifications mentioned in the corresponding drawing.	SET	1	7,996.00	7,996.00
6	R6	Supplying and placing of custom fabricated Stainless steel WORK TABLE WITH SINK of size 1400 mm X 600 mm X (850+150) mm with 14 SWG Stainless steel top with splash back and Ø200 mm cut out for garbage chute on LHS, sink of size 650 mm X 450 mm X 300 mm deep, strainer basket, frame work, legs and cross bracings i/c connections etc complete as per the specifications mentioned in the corresponding drawing	SET	1	34,338.00	34,338.00
TOTAL OF RECEIVING AREA						8,42,353.00
PART XIII		OIL STORAGE				
1	OS1	Supplying and placing custom fabricated OIL PALLET TWO TIERS of size 1400 mm X 750 mm X 1200 mm made up of 25 mm x 25 mm stainless steel square pipes at 75 mm distance from each other. It shall also be provided with 16 SWG SS oil drip tray, castors with brakes etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	20,846.00	62,538.00
2	OS2	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size 1200 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	35,552.00	35,552.00
TOTAL OF OIL STORAGE						98,090.00
PART XIV		GRAIN STORAGE				
1	GS1	Supplying and placing of custom fabricated GRAIN PALLET of size 2000 mm X 1050 mm X 300 mm with 14 SWG stainless steel corner pieces(150mm X 150 mm) and 25 mm X 25 mm SS square pipes at 75 mm distance from each other, legs with nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	4	19,632.00	78,528.00
TOTAL OF GRAIN STORAGE						78,528.00
PART XV		DRY STORAGE				
1	ST1	Supply, Installation, Testing & Commissioning of CHEST FREEZER of minimum 285 liters capacity and internal Temperature Range of -24°C to + 8°C, suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	32,481.00	64,962.00
2	ST2	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size 1050 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	8	31,875.00	2,55,000.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
3	ST3	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK THREE SHELVES of size 1500 mm X 600 mm X 1800 mm with 3 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	3	36,728.00	1,10,184.00
4	ST4	Supplying and placing of custom fabricated STAINLESS STEEL BIN ON DOLLEY of size 400 mm X 500 mm X 750 mm with 16 SWG SS 304 bin and lid castors,collapsible handles, SS plate, frame work and castors with brakes etc complete as per the specifications mentioned in the corresponding drawing	SET	9	26,949.00	2,42,541.00
5	ST5	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size 1200 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	35,552.00	71,104.00
TOTAL OF DRY STORAGE						7,43,791.00
PART XVI		WASTE BIN				
1	WB2	Supplying and placing of custom fabricated Stainless steel BUSSING TROLLEY of size 1050 mm X 700 mm X 1000 mm with 14 SWG SS 304 top tray type shelve, 2 nos. 16 SWG SS removable tray of size 300 mm X 600 mm X 150 mm & 600 mm X 600 mm X 150 mm and 16 SWG SS tray type bottom shelves, handle, SS plate and castors with brakes etc complete as per the specifications mentioned in the corresponding drawing.	SET	6	35,552.00	2,13,312.00
2	WB3	Supplying and placing of Heavy duty platform WEIGHING SCALE FLOOR MODEL upto150 Kg load capacity with accuracy of 10 gm and Stainless steel platform of minimum size 400 mm X 500 mm suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	15,735.00	31,470.00
TOTAL OF WASTE BIN						2,44,782.00
PART XVII		WATER COOLER SECTION				
1	WC1	Supplying and placing of custom fabricated stainless steel GLASS MOBILE TABLE of size 900 mm X 600 mm X 850 mm with 2 no Undershelves ,legs with castors with brakes and frame work etc complete as per the specifications mentioned in the corresponding drawing	SET	2	26,949.00	53,898.00
TOTAL OF WATER COOLER SECTION						53,898.00
PART XVIII		FIRST FLOOR DRY STORAGE				
1	STF1	Supplying and placing of Heavy duty platform WEIGHING SCALE FLOOR MODEL upto150 Kg load capacity with accuracy of 10 gm and Stainless steel platform of minimum size 400 mm X 500 mm suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	1	15,735.00	15,735.00
2	STF2	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size 1200 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant from each other ,uprights with adjustable nylon bullet feet etc complete as per the specifications mentioned in the corresponding drawing.	SET	7	35,552.00	2,48,864.00
3	STF3	Supply, Installation, Testing & Commissioning of CHEST FREEZER of minimum 285 liters capacity and internal Temperature Range of -24°C to + 8°C, suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	34,795.00	69,590.00
TOTAL OF FIRST FLOOR DRY STORAGE						3,34,189.00
PART XIX		FIRE SUPPRESSION SYSTEM				
1	FA1	Supply, Installation, testing and commissioning of EXHAUST HOOD FIRE SUPPRESSION SYSTEM HOOD NO - EX1,EX2,EX3.EX4 & EX5 , with wet chemical agent with both automatic actuation and manual actuation system through a pull station. The system including all of its components, shall be UL listed. The system shall be complete with all components like supply and actuation unit including manual pull station, control panel, Heat detection system, Extinguishing installations like nozzle for ranges, plenum and cut off, SS pipe fittings, etc. The system should also generate Audio Visual alarm in case of fire etc complete as required. The system should provide 100% protection as required	SET	1	25,45,332.00	25,45,332.00
TOTAL OF FIRE SUPPRESSION SYSTEM						25,45,332.00

ITEM NO	EQUIPMENT NO.	DESCRIPTION OF ITEM	UNITS	QTY	RATE-RS	AMOUNT-RS
PART XX		MISCELLANEOUS				
1	M2	Supply, Installation, Testing & Commissioning of zapper PEST-O-FLASH with minimum 2 no. of UV tubes of wattage 15 W-20 W/tube, 17" ~ 24" long tube enclosed in powder coated GI body, suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	14	12,015.00	1,68,210.00
2	M3	Supply , Installation, Testing & Commissioning of custom fabricated Stainless steel knee operated HAND WASH SINK of size 450 mm X 375 mm X (225+150) mm with splash back having 16 SWG SS sunk in top of size 300 mm X 225 mm X 200 mm deep i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	5	18,383.00	91,915.00
3	M3A	Supply, Installation, Testing & Commissioning of HAND DRYER Construction : Stainless Steel # 304, Matt Finish Mounting : Wall Mounted Operation : Automatic, Hand Dry Time : 9S, Auto Cutoff : 60 seconds, Noise Leve : 60-70db, Motor : brush motor Speed : 3000r/min, Voltage : 220-240V, Rated Power : 1000W, Current : 6A, Protection : IPx4 as per the specifications mentioned in the corresponding drawing.	SET	5	23,016.00	1,15,080.00
4	M4	Supply, Installation, Testing & Commissioning of AIR CURTAIN of width 1800 mm with 10-12 m/s air velocity, noise level < 75 db, Stainless Steel body including connections as per the specifications mentioned in the corresponding drawing.	SET	2	53,824.00	1,07,648.00
5	M5	Supply, Installation, Testing & Commissioning HIGH PRESSURE CLEANING MACHINE with flow rate of 600 LPH and pressure of 130 bar with ceramic plunger triplex pump with all standard set of accessories, suitable for operation on 230 volts/50 Hz single phase A.C. supply i/c connections etc complete as per the specifications mentioned in the corresponding drawing.	SET	2	9,74,915.00	19,49,830.00
6	M6	Supply, Installation, Testing & Commissioning of HOSE REEL Enclosed stainless steel hose reel, stainless steel rear trigger watergun and swivel with 5/16" orifice, 3/8" x 50' heavy-duty non-marking hose, ratcheting system, multi-fit bracket, adjustable hose bumper and 3/8" NPT female inlet. • Pressure Max: 125 psi (8.62 bar) • Pressure Min: 20 psi (1.38 bar) • Temperature Max: 200 F (93.33°C) • Temperature Min: 40 F (4.44°C) • Water Gun Flow: 3.7 GPM (14.00 L/min) as per the specifications mentioned in the corresponding drawing.	SET	2	2,26,397.00	4,52,794.00
7	M9	Supply , Installation, Testing & Commissioning of WATER COOLER 60 LTR of size 500 mm X 500 mm X 1050 mm Brand Ezyfrost, Storage Capacity 100L, Body Material Stainless Steel Voltage 230V / 50Hz, Power 535W, Temp. Range 6 Degree, Taps 1, Climate Class 42 DegreeC Country of Origin Made in India as per the specifications mentioned in the corresponding drawing.	SET	29	47,428.00	13,75,412.00
8	M10	Supply , Installation, Testing & Commissioning of WATER COOLER 100 LTR of size 700 mm X 500 mm X 1200 mm Brand Ezyfrost, Storage Capacity 100L, Body Material Stainless Steel Voltage 230V / 50Hz, Power 535W, Temp. Range 6 Degree, Taps 2, Climate Class 42 DegreeC Country of Origin Made in India as per the specifications mentioned in the corresponding drawing.	SET	2	68,133.00	1,36,266.00
		TOTAL OF MISCELLANEOUS				43,97,155.00
		Total Amount -Rs			TOTAL	3,80,84,694